

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-22700-00-00
Spot: SWNENW Sec/Twnshp/Rge: 5-20S-10W
4025 feet from S Section Line, 3330 feet from E Section Line
Lease Name: RINGWALD Well #: B-5
County: RICE Total Vertical Depth: 3297 feet

Operator License No.: 30380
Op Name: HUPFER OPERATING, INC.
Address: PO BOX 3912
SHAWNEE, KS 66203

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3294	2220	100 SX
SURF	8.625	250		180 SX
T1	2.875	3200		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/02/2015 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JONATHAN HILL Witness Type: PARTIAL
Date/Time Plugging Completed: 06/02/2015 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND OPEN HOLE TO 3150' AND CAP WITH 5 SX'S CEMENT. CUT CASING OFF AT 2220' AND PULL TO 1300' AND PUMP 35 SX'S CEMENT WITH CC. PULL CASING ON UP TO 900', LET SET FOR 1 HOUR. TAGGED CEMENT AT 1230'. PUMPED 35 SX'S AT 900', PULLED CASING TO 300' AND CIRCUALTED CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3294	3297		OPEN HOLE

Received
KANSAS CORPORATION COMMISSION
JUN 12 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. COPELAND # C-41300

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

6/24/15 ckm

✓