

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-07151-00-01  
Spot: SWSWNE Sec/Twnshp/Rge: 1-14S-15W  
2790 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: A DUMLER Well #: 1  
County: RUSSELL Total Vertical Depth: 3116 feet

Operator License No.: 30317  
Op Name: J.H. R., INC.  
Address: 533 WASHINGTON RD STE 100  
BRIDGEVILLE, PA 15017

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3047		234 SX
SURF	8.62	2766		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/05/2015 9:00 AM  
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING  
Proposal Rcvd. from: WARD CRAIG Company: J.H.R. Phone: (785) 483-2025

Proposed Plugging Method: Ordered 600 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/05/2015 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3040' and pumped 9 sx gel followed by 75 sx cement w/200 # hulls. Pulled tubing to 2400' and pumped 250 sx cement w/200 # hulls. Pulled tubing to 1450' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 900' and pumped 100 sx cement. Circulated cement to surface. Pulled tubing and topped off w/75 sx cement. Surface pipe full of cement.

GPS: 38.86409 -098.93649

Perfs:

Top	Bot	Thru	Comments
3047	3085		

Remarks: GLOBAL CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

6/24/15 CKM

CM

KCC WICHITA

JUN 18 2015

RECEIVED

JUN 18 2015