

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-07152-00-00  
Spot: SESWNENE Sec/Twnshp/Rge: 1-14S-15W  
2970 feet from N Section Line, 1650 feet from W Section Line  
Lease Name: DUMLER A Well #: 2  
County: RUSSELL Total Vertical Depth: 1250 feet

Operator License No.: 30317  
Op Name: J.H. R., INC.  
Address: 533 WASHINGTON RD STE 100  
BRIDGEVILLE, PA 15017

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| PROD   | 6.62 | 2614       |             |          |
| SURF   | 8.62 | 2772       |             | 100 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/04/2015 9:00 AM  
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING  
Proposal Rcvd. from: WARD CRAIG Company: J.H.R. Phone: (785) 483-2025

Proposed Plugging Method: Ordered 300 sx Common cement w/3% cc, 250 sx 60/40 pozmix 4% gel cement and 500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/04/2015 4:00 PM KCC Agent: BRUCE RODIE

**Actual Plugging Report:**

Went in to perforate and gun stuck at 550'. Pulled gun up to 450' and perforated top perforation. Pulled gun. Ran tubing to 905'. Also ran in a slim line gun and perforated at 905'. Ran tubing to 1240' and pumped 300 sx common cement w/3% cc followed by 100 sx 60/40 pozmix 4% gel cement w/500 # hulls. Tubing stuck at 1240'. Pumped water behind cement and got tubing free. Pulled tubing and waited 2 hours. Ran tubing to 540' and pumped 50 sx cement. Circulated cement to surface on casing. Pulled tubing and circulated cement to surface on surface pipe w/50 sx cement.

GPS: 38.86465 -098.93378

**Perfs:**

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2772 | 2775 |      |          |

Remarks: GLOBAL CEMENTING

Plugged through: TBG

6/24/15 CKM

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

KCC WICHITA

JUN 10 2015

JUN 18 2015

RECEIVED