

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-23368-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 18-14S-18W
2199 feet from S Section Line, 2380 feet from E Section Line
Lease Name: ROHR Well #: 1
County: ELLIS Total Vertical Depth: 3753 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3742		150 SX
SURF	8.625	452		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/05/2015 11:30 AM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: TODD L. DINKEL Company: G L M CO. Phone: (785) 639-5415

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement, 10 sx gel and 700 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/05/2015 5:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1775', 1365' and 655'. Ran tubing to 3560' and pumped 10 sx gel followed by 75 sx cement w/200 # hulls. Pulled tubing to 1800' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 800' and pumped 100 sx cement w/150 # hulls. Cement circulated. POOH. TOC 450' - 500' down. Pumped a total of 100 sx cement w/50 # hulls to top off casing. Braden head was dug out and found to be full of cement. Checked full up on 06/08/2015 and cement was down 5'. Todd Dinkel cut off casing and restored well site.

GPS: 38.833630 -099.36358

Perfs:

Top	Bot	Thru	Comments
3603	3603		
3588	3588		
3568	3568		
3535	3538		
3483	3483		
3482	3486		
3458	3458		
3436	3436		
3426	3426		
3424	3427		

Remarks: GLOBEL CEMENTING TICKET # 1670

Plugged through: TBG

6/24/15 CKM

District: 04

Signed Ray Dinkel
(TECHNICIAN) CM

JUN 09 2015

KCC WICHITA

JUN 18 2015

RECEIVED