

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-20332-00-01
Spot: SWSWNE Sec/Twnshp/Rge: 30-33S-28W
2983 feet from S Section Line, 2351 feet from E Section Line
Lease Name: MOHLER UNIT Well #: 6
County: MEADE Total Vertical Depth: 5725 feet

Operator License No.: 31652
Op Name: NORSTAR PETROLEUM, INC.
Address: 88 INVERNESS CIR E. UNIT F104
ENGLEWOOD, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5724	1933	WITH 200 SX CMT
SURF	8.625	1494		WITH 600 SX CMT

Well Type: EOR UIC Docket No: E26993.3 Date/Time to Plug: 06/08/2015 9:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SQUEEZE PERFS WITH 25 SX CMT & 200# HULLS. PLUG AT 1530' WITH 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: PARTIAL
Date/Time Plugging Completed: 06/09/2015 4:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SQUEEZE PERFS WITH 25 SX CMT & 200# HULLS. 1ST PLUG AT 1530' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5614	5629		
5601	5608		

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED CLASS A CEMENT BY SARGENT LILLARD.

Plugged through: CSG

6/24/15

District: 01

Signed Larry A Harris PART II
(TECHNICIAN)

RECEIVED
JUN 12 2015
KCC DODGE CITY

SA

Received
KANSAS CORPORATION COMMISSION

JUN 15 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

UIC