

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-24284-00-00
Spot: NESENE SW Sec/Twnshp/Rge: 15-7S-20W
1941 feet from S Section Line, 2581 feet from W Section Line
Lease Name: RATLIFF-METHODIST Well #: 1
County: ROOKS Total Vertical Depth: 3515 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 217 | | 150 sx |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/03/2015 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 290 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RAY DINKEL Witness Type: NONE
Date/Time Plugging Completed: 06/03/2015 9:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

1st plug @3452 w/50 sx
2nd plug @1590 w/50 sx
3rd plug @920 w/100 sx
4th plug @270 w/50 sx
5th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

6/24/15 CKM

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

JUN 05 2015

KCC WICHITA

JUN 18 2015

RECEIVED

Form CP-2/3