

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-023-20312-00-00
Spot: NENENE Sec/Twnshp/Rge: 10-1S-38W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: CHRISTENSEN Well #: 4
County: CHEYENNE Total Vertical Depth: 4500 feet

Operator License No.: 3152
Op Name: POE SERVICING INC
Address: PO BOX 115
OBERLIN, KS 67749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4495		
SURF	8.625	200		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/04/2015 9:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: RUBY POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: 8 5/8" surface casing set at 200' w/ unknown amount of cement. 5 1/2" production casing set at 4495' w/ unknown amount of cement. TD 4500. Perforations are unknown. LKC was reported to have been tested.

Plugging Proposal Received By: CASE MORRIS Witness Type: PARTIAL
Date/Time Plugging Completed: 05/07/2015 7:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

Perforated production casing at 3030' and 2230'. Ran tubing to 4400' and pumped 10 sx gel followed by 50 sx cement. Pulled tubing to 3030' and pumped 145 sx neat cement from redi mix company. Pulled tubing to surface and shut down at 6:30pm.
05/07/2015- Tagged cement at 1120' and pumped 100 sx cement. CWC. Pulled tubing to surface and topped casing off with 10 sx cement. Connected to 8 5/8" surface casing and pumped 15 sx cement. Pressured to 300 psi.

GPS: 39.98705N -101.56185W

Remarks: COMPANY TOOLS

Plugged through: TBG

6/24/15 ckm

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

CM

KCC WICHITA

JUN 18 2015

RECEIVED

MAY 19 2015

Form CP-2/3