

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-01028-00-00
Spot: SWNESW Sec/Twnshp/Rge: 32-13S-14W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: BOXBERGER Well #: 3
County: RUSSELL Total Vertical Depth: 3317 feet

Operator License No.: 32322
Op Name: ROBERTS, DENIS F.
Address: 3904 FAIRWAY DR BOX 1252
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3300		
PROD	5.5	3292		75 SX
SURF	8.625	211		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/28/2015 9:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DEINIS F. ROBERTS Company: DENIS F ROBERTS Phone: (785) 625-8526

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 10 sx gel and 500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/28/2015 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1425'. Ran tubing to 3250'. Plugged tubing up and hung up. Pulled tubing to 2700'. Tubing came free and clean pumped 3 sx gel followed by 50 sx cement. Pulled tubing to 1500' and pumped 150 sx cement. Cement circulated to pit. POOH and pumped 20 sx cement. Casing stayed full. Dug braden head out and found to be full of cement. 4.5" x 5/5" annulus was full of cement.

GPS: 38.87557 -098.90437

GPS: 38.87557 -098.9437

Perfs:

Top	Bot	Thru	Comments
3298	3317		

Remarks: ALLIED CEMENTING TICKET # 55774

Plugged through: TBG

6/24/15 CKM

District: 04

Signed Ray A. Dinkel
(TECHNICIAN)

CM

KCC WICHITA

JUN 18 2015

RECEIVED

JUN 01 2015