


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County. Sec. 15 Twp. 29 Rge. 9 (E) W. (W)
Location as "NE/CNW4SW4" or footage from lines 330' S. & 990' E. of Cen.
Lease Owner Cities Service Oil Company
Lease Name Schwartz Well No. 1
Office Address Box 144, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed October 1, 1954
Application for plugging filed October 17, 1957
Application for plugging approved October 21, 1957
Plugging commenced October 30, 1957
Plugging completed November 5, 1957
Reason for abandonment of well or producing formation No longer commercially productive.
If a producing well is abandoned, date of last production October 14, 1957
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Viola Depth to top 4500 Bottom 4530 Total Depth of Well 4530 Feet
Show depth and thickness of all water, oil and gas formations. P. B. T. D. 4514'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	309'	None
				5-1/2"	4530'	3052'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- 4514-4300', sand.
- 4300-4260', 5 sacks cement.
- 4260- 300', mud.
- 300-285', rock.
- 285-225', 20 sacks cement.
- 225- 35', mud.
- 35- 30', rock.
- 30' to surface, 10 sacks cement.

RECEIVED
COMMISSION
NOV 13 1957 11-13-57
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor G. E. Shull Casing Pulling Company
Address Box 558, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
V. M. Conover (employee of owner) or Owner/Operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. M. Conover
Box 144, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of November, 19 57

N. G. Smith
Notary Public.

My commission expires March 12, 1959.

PLUGGING
FILE SEC. 15 T. 29 R. 9W
BOOK PAGE 54 LINE 31

Handwritten mark

WELL RECORD

Company Cities Service Oil Company Well No. 1 Farm Schwartz
 Location 330' South & 990' East of Center Sec. 15 T. 29 R. 9W
 Elevation 1695 (1693 Cr.) County Kingman State Kansas
 Drlg. Comm. September 17, 1954 Contractor Prime Drilling Company
 Drlg. Comp. October 1, 1954 Acid None
 T. D. 4530' Initial Prod. Physical Potential: 82 oil, 39 water, 24 hrs. (10-29-54)
 F.S.T.D. 4514'

CASING RECORD:

8-5/8" @ 309' con. 225 air cement
 5-1/2" @ 4530' con. 150 air cement

FORMATION RECORD:

sand	0-90
red bed	560
shale & cholla	1345
anhydrite	1375
shale & lime	1500
lime & shale	2160
shale & lime	2750
lime & shale	3195
lime	4030
lime & shale	4206
lime & chert	4295
lime	4340
lime & shale	4470
lime	4530

4530 HTD = 4530 BLM

Reebner	3357'
Lansing	3565'
Mississippi	4210'
Kinderhook	4322'
Viola	4500'
Penetration	30'
Total Depth	4530'

Drilled cement to 4514 S. I. M.

Perf. 13 shots 4499-4502.

646' fluid in 2 hrs.

SLOPE TESTS (SURF SHOT):

325'	3/4°
500'	3/4°
1000'	3/4°
1500'	1°
2000'	0°
2500'	1/2°
3000'	3/4°

KINGMAN COUNTY
 CONSERVATION DIVISION
 WINNIE, KANSAS
 OCT 2 1954

PLUGGING			
FILE	SEC	T	R
	15	29	9W
BOOK	PAGE	LINE	
	54	31	