

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County. Sec. 15 Twp. 29S Rge. 9 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE/SW/NE

Lease Owner Aurora Gasoline Company

Lease Name Hageman Well No. #1

Office Address 1107 Union National Building, Broadway and Douglas

Character of Well (completed as Oil, Gas or Dry Hole) Wichita, Kansas

Date well completed 19

Application for plugging filed Yes 19

Application for plugging approved Yes 19


Plugging commenced 11-10 19 58

Plugging completed 11-15 19 58

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Fred Hampel

Producing formation Depth to top Bottom Total Depth of Well 4535' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"		
				5 1/2"		3,029'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Measured into T.D. 4535'.
Plugging started 11-10-58. Finished 11-15-58.
Plugged off bottom and sanded to 4480'. Dumped 5 sacks cement.
Shot 5 1/2" casing at 3,029'. Worked and shot pipe. Jetted mud and loaded hole. Squeezed well, using 100 sacks cement. Well completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
134 221, Great Bend, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of November, 1958

Betty S. Edman
Notary Public.

My commission expires November 8, 1960.

RECEIVED
STATE CORPORATION COMMISSION

NOV 19 1958

PLUGGING
FILE SEC 15 T. 29 R. 9W
BOOK PAGE 143 LINE 28

HAGEMAN #1

Casing Record:

8-5/8" - 137' w/90 sacks cement
 5-1/2" - 4535'

Company: Aylward Drilling Company et al

Contractor: Aylward Drilling Company

Commenced: November 26, 1954

Completed: December 9, 1954

Location:
 NE SW NE
 Section 15-296-9W
 Kingman County, Kansas

Elevation:
 1702 K.B.
 1700 D.F.

	FROM	TO	REMARKS
Surface Clay	0	15	
Shale & Shells	15	137	
Red Bed	137	320	
Red Bed	320	480	
Shale & Shells	480	1000	JDST#1 4503 -4508 , Open 30 minutes, good blow, rec. 930' fluid (810' oil / 120' SW), FP 135-360#, BHP 1500#/30min., Hyd. 2430# (10# mud).
Blue Shale & Lime Shells	1000	1200	
Salt & Anhydrite Lime Strks.	1200	1250	
Shale & Lime	1250	1380	
Anyhydrite Lime	1380	1440	
Lime & Shale	1440	1645	
Lime & Shale	1645	1815	
Lime with Shale Strks	1815	1960	
Lime & Shale	1960	2050	
Lime	2050	2080	
Lime & Strks. Shale	2080	2130	
Lime Shale & Shells	2130	2215	
Lime	2215	2260	
Lime & Shale	2260	2360	
Shale & Lime	2360	2595	
Shale & Lime	2595	2670	
Lime & Shale	2670	2725	
Lime & Shale	2725	3215	
Lime w/ Shale Strks	3215	3415	
Lime & Shale (Sandy)	3415	3552	
Lime Shale Str. Sand	3552	3620	
Lime	3620	3673	
Lime	3673	3727	
Lime	3727	3884	
Lime Shale Strks Salt	3884	3953	
Lime & Shale	3953	4157	
Shale & Chat	4157	4260	
Chat & Lime	4260	4340	
Shale & Lime Strks.	4340	4416	
Shale & Lime	4416	4508	
Shale & Lime Chert	4508	4535 R.T.D.	

CABLE TOOL DATA:

Perforated 20 holes from 4501 to 4506

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 7 1954
 CONSERVATION DIVISION
 Wichita, Kansas

TOPS:

HEEBNER	3341
TORONTO	3356
DOUGLAS	3377
LANSING	3558
MISSISSIPPIAN	4199
VIOLA	4502

PLUGGING
 FILE SEC. 15 T. 29 R. 9W
 BOOK PAGE 143 LINE 28

I certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse

Subscribed and sworn to before me this _____ day of _____, 1955.

Notary Public

My Commission Expires: December 11, 1957.