


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Kingman County, Sec. 15 Twp. 29 Rge. 9 (E) (W) x
Location as "NE/CNW/SW" or footage from lines. SW NW NW
Lease Owner. Okmar Oil Co.
Lease Name. Hageman Well No. #1
Office Address. 1130 Vickers KSB&T Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed. 19
Application for plugging filed. 2-15-72 19
Application for plugging approved. 19
Plugging commenced. 2-24-72 19
Plugging completed. 2-28-72 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production. 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well. G. R. Riberstein 4525'
Producing formation. Depth to top. Bottom. Total Depth of Well. 4403' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
					5x7x24	
				5 1/2"	4524'	3555.08'
				8 5/8"	204'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made plug back with sand to 4470'. Mixed and ran 5 sacks cement thru dump trailer.
Mudded hole to 235', set 15' rock bridge. Filled hole with 3 1/2 yards ready-mix
from 220' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAR 1 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor. Southwest Casing Pulling Co.
Address. Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29 day of February, 1972

My commission expires



Sidney D. Miller
Notary Public.

DRILLERS' LOG

#1 Hageman
SW NW NW Section 15-293-0W
Kingman County, Kansas

FROM	TO	Description
0	60	Soil and sand
60	135	Red bed
135	207	Red bed and shalts
207	270	Red shale
270	788	Shale and Red bed
788	827	Anhydrite
827	1287	Shale
1287	1575	Shale and salt
1575	1735	Lime
1735	2358	Lime and shale
2358	2445	Shale
2445	2527	Shale
2527	2596	Lime and shale
2596	2631	Lime
2631	2692	Lime and shale
2692	2691	Lime
2691	2703	Lime
2703	2830	Lime and shale
2830	2852	Lime
2852	4187	Lime and shale
4187	4264	Miscislopien
4264	4293	Lime
4293	4415	Lime and shale
4415	4486	Shale
4486	4525	Viola
	4525	Rotary Total Depth

COMMENCED: 4-24-56

COMPLETED: 5-11-56

Set 204' of 3-9/8" surface casing with 150 sacks cement, 200# calcium chloride and 200# jet.

Set 4524' of 5-1/2" casing with 150 sacks cement and 200# jet.

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1972
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS |
 | SS
COUNTY OF SEDGWICK |

I hereby affirm that the above and foregoing is a true and correct copy of the formations encountered on the #1 Hageman, SW NW NW Section 15-293-0W, Kingman County, Kansas, as reflected by the daily drilling reports.

ANSCHUTZ DRILLING CO., INC.

By: Shirley Salley
Shirley Salley

Subscribed and sworn to before me this 14th day of May, 1956.

My Commission Expires: May 24, 1956

Wilma V. Shipman
Notary Public