


2

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec. 14 Twp. 29 Rge. 9 (E) W. (W)
Location as "NE/CNW/SW" or footage from lines SW NW NW
Lease Owner Cities Service Oil Company
Lease Name Mueller "E" Well No. 1
Office Address Box 308, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas Well
Date well completed August 3 19 54
Application for plugging filed May 15 19 68
Application for plugging approved May 16 19 68
Plugging commenced June 3 19 68
Plugging completed June 4 19 68
Reason for abandonment of well or producing formation Depleted formation.

If a producing well is abandoned, date of last production December 1 19 68
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. J. Warren
Producing formation Indian Cave Depth to top 2390 Bottom Total Depth of Well 4509 Feet
Show depth and thickness of all water, oil and gas formations. P. B. T. D. 2459 Feet

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	345'	0
				5-1/2"	2459'	1650'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

2459-330', mud.
330-320', rock bridge.
320-245', 25 sacks cement.
245- 40', mud.
40- 30', rock bridge.
30' to base of cellar, 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1968
CONSERVATION DIVISION
Wichita, Kansas

NOTE: This well was formerly Mueller "C" #2.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
W. J. Devaney (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. J. Devaney
Box 308, Great Bend, Kansas
(Address)

Subscribed and sworn to before me this 24th day of June, 19 68



Robert L. Gilchrist
Notary Public.

WELL RECORD

Company Cities Service Oil Co. Well No. 2 Farm Mueller #C
 Location 990' South & 330' East of NW Cor. Sec. 14 T. 29 R. 9W
 Elevation 1697 (1694 Cr.) County Kingman State Kansas
 Drlg. Comm. July 17, 1954 Contractor Prime Drilling Company
 Drlg. Comp. August 3, 1954 Acid None
 T. D. 4509' Initial Prod. B.H.P. Gauge Potential: 2008 oil, no water, 24 hrs.
 B.T.D. 4501' (8-24-54)

CASING RECORD:

8-5/8" @ 341' cem. 225 sx cement
 5-1/2" @ 4509' cem. 125 sx cement

FORMATION RECORD:

sand	0-65
clay	80
red rock & shells	135
red bed & sand	242
red bed & shale	620
shale & shells	1405
anhydrite	1420
lime & shale	1785
lime w/ streaks shale	1960
lime & shale	2090
shale & lime	2690
lime & shale	3040
shale	3049
lime & shale	3250
lime	3305
shale & lime	3470
shale	3535
lime & shale	3580
lime	4005
shale & lime	4180
lime	4202
lime, chert & shale	4265
shale & lime	4295
lime	4330
lime & shale	4455
shale	4475
lime	4510

4510 RTD = 4509 SLM

Corr. Lansing	3547'
Corr. Mississippi	4191'
Corr. Kinderhook	4299'
Corr. Viola	4474'
Penetration	35'
Total Depth	4509'

Drilled cement to 4501 S.L.M.

Perf. 45 shots 4474-85; good show
 gas in 4 mins.
 4151' oil in 2 hrs.

SLOPE TESTS (SURE SHOT):

312'	1°
500'	1/2°
1000'	1/2°
1500'	1-1/4°
2000'	1/2°
2500'	1°
3000'	1/2°
3500'	3/4°
4000'	1-1/2°

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 16 1968
 CONSERVATION DIVISION
 Wichita, Kansas