

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 14 Twp. 29 Rge. 9 (SE) (W)

Location as "NE/CNW/SW" or footage from lines. SW/NE/NW

Lease Owner Aurora Gasoline Company

Lease Name Mueller Well No. #2

Office Address 1107 Un. Natl. Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19 \_\_\_\_\_

Application for plugging filed Yes 19 \_\_\_\_\_

Application for plugging approved Yes 19 \_\_\_\_\_

Plugging commenced \_\_\_\_\_ 8-24 19 58

Plugging completed \_\_\_\_\_ 8-29-19 58

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Fred Hampel

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4509' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"		
				5 1/2"		3,612'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Measured into T.D. 4509'.  
Plugging started 8-24-58. Finished 8-29-58.  
Plugged off bottom and sanded back to 4450'. Dumped 5 sacks cement.  
Shot 5 1/2" casing at 3,612'. Circulated and spotted 70 bbls oil.  
Pulled pipe out of hole. Squeezed well, using 100 sacks cement.  
Well completed.

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.  
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J.O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
Box 221, Great Bend, Kans. (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of September, 19 58

My commission expires November 8, 1960. Betty S. Edman Notary Public.

PLUGGING  
FILE SEC 14 T. 29 R. 9W  
BOOK PAGE 122 LINE 7

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 10 1958  
CONSERVATION DIVISION  
KANSAS

MUELLER NO. 2

Casing Record: Company: Aylward Drilling Co. et al. Location: SW NE NW 14-29-9W  
Kingman County, Kans.  
8 5/8" - 146' Contractor: Aylward Drilling Co.  
5 1/2" - 4506' Completed: Sept. 9, 1954  
Commenced: August 28, 1954  
Completed: Sept. 9, 1954 Elevation: 1685 K.B.  
1682 D.F.

	<u>From</u>	<u>To</u>	<u>Remarks:</u>
Sand	0	60	Set 146' casing w/125 sacks cement and 2 sacks C.C.
Shale	60	80	
Red Bed	80	450	
Red Bed, Shale & Shells	450	600	<u>GEOLOGICAL TOPS</u> Lansing 3540 Mississippian 4180 Viola 4467 R.T.D. 4505
Shale & Shells	600	1375	
Lime & Shale	1375	2220	
Lime & Sandy Lime	2220	2357	
Shale & Lime	2357	2575	
Lime	2575	2717	
Lime & Shale	2717	3020	
Lime	3020	3385	
Shale, Lime & Chert	3385	3465	
Lime, Sand & Shale	3465	3570	
Lime	3570	4115	<u>CABLE TOOL DATA</u> Perforated 45 holes from 4476 to 4468 Swabbed well to make it flow. Put on pump.
Shale & Lime	4115	4189	
Mississippi Chat	4189	4253	Set 4506' 5 1/2" casing w/150 sacks cement.
Mississippi Lime	4253	4257	
Lime	4257	4468	
Chert & Dolomite	4468	4478	
Lime	4478	4509 T.D.	

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

J.A. Aylward

Subscribed and sworn to before me this 6th day of August, 1958.

STATE COMMISSION  
AUG 9 1958  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 14 T. 29 R. 9W  
BOOK PAGE 122 LINE 7