


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kingman County. Sec. 14 Twp. 29 Rge. 9 (E) W. (W)  
Location as "NE/CNW/SW" or footage from lines 330' S. & 990' E. of N/4 Cor.  
Lease Owner Cities Service Oil Company  
Lease Name Mueller "D" Well No. 1  
Office Address Box 144, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed November 30, 19 54  
Application for plugging filed February 20, 19 59  
Application for plugging approved February 25, 19 59  
Plugging commenced February 27, 19 59  
Plugging completed March 9, 19 59  
Reason for abandonment of well or producing formation Depleted formation.



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production February 20, 19 59  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation Viola Depth to top 4491 Bottom 4521 Total Depth of Well 4521 Feet  
Show depth and thickness of all water, oil and gas formations. P. B. T. D. 4509 Feet

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	312'	None
				5-1/2"	4521'	3317'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.  
4509-4475', river sand.  
4475-4435', 5 sacks cement.  
4435- 300', heavy mud.  
300- 240', rock bridge and 20 sacks cement.  
240- 30', heavy mud.  
30' to base of cellar, rock bridge and 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 13 1959  
3-13-59  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor C. E. Shull Casing Pulling Company  
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
V. M. Conover (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. M. Conover  
Box 144, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of March 19 59  
W. D. Smith  
Notary Public.

My commission expires March 12, 1963

PLUGGING  
FILE SEC. 14 T 29 R 9W  
BOOK PAGE 16 LINE 29

# WELL RECORD

Company Cities Service Oil Company Well No. 1 Farm Mueller "D"  
 Location 330' South and 990' East of N/4 Cor. Sec. 14 T. 29 R. 9W  
 Elevation 1704 (1701 Gr.) County Kingman State Kansas  
 Drlg. Comm. October 28, 1954 Contractor Barbour Drilling Company  
 Drlg. Comp. November 14, 1954 Acid 250 gallons 11-21-54  
 T. D. 4521' Initial Prod. Physical Potential (Flow): 238 oil, no water, 2 1/2 hrs.  
 P. B. T. R. 4509' (11-30-54)

CASING RECORD:

8-5/8" @ 312' cas. 225 sacks cement  
 5-1/2" @ 4521' cas. 150 sacks cement

FORMATION RECORD:

clay & sand	0-90
red bed	140
red bed & shale	600
red bed & shells	760
shale & shells	1360
anhydrite	1385
shale & shells	1410
shale & lime	1860
lime & shale	2110
shale & shells	2295
shale & lime	2475
shale	2607
shale & shells	2680
lime	2745
shale & lime	2935
lime & shale	3205
lime	3285
lime & shale	3355
shale, sand & lime	3410
shale & lime	3450
shale & sand	3550
lime	4000
lime & shale	4185
lime, shale & chert	4235
cherty lime	4305
lime & shale	4355
shale	4490
shale & lime	4499
chert & lime	4523

4523 STD = 4521 STD

Corr. Lansing	3556'
Corr. Mississippi	4212'
Corr. Kinderhook	4318'
Corr. Viola	4491'
Penetration	30'
Total Depth	4521'

Drilled cement to 4509 S. L. M.  
 Loaded hole with 40 bbls. oil.

Port. 16 jet shots 4491-95; no fillup.

SYFO:	260'	00
	500'	10
	1000'	10
	1500'	00
	2000'	00
	2500'	00
	3000'	10
	3500'	00
	4000'	00

RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB 24 1954

**PLUGGING**

FILE SEC 14 T. 29 R. 9W

BOOK PAGE 16 LINE 29