

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Pratt SEC. 35 TWP. 28S RGE. 14W E/W  
Location as in quarters or footage from lines:  
C S/2 SW SE

		35	

Lease Owner Vincēt Oil Corporation  
Lease Name Omo Well No. 1  
Office Address 125 N. Market, #1110, Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole.  
Date Well Completed June 14, 1983  
Application for plugging filed 6/20/83  
Plugging commenced 6/14/83  
Plugging completed 6/14/83  
Reason for abandonment of well or producing formation  
Dry Hole

Locate Well  
correctly on above  
Section Pratt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice V. Leslie  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4680'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		0'	411'	8-5/8"	404.39'	None

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Plugged with 50 sacks cement at 4530';  
50 sacks cement at 840'; 40 sacks cement  
at 450'; solid bridge plug and 10 sacks  
cement at 40'; 15 sacks cement in rat hole;  
and 10 sacks cement in mouse hole.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dowell Cementing Co.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

John D. Knightley, Agent (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
221 S. Broadway, Wichita, KS 67202  
(Address)



SUBSCRIBED AND SWORN TO before me this 20th day of June, 1983

Stella J. Lipp  
Notary Public.

My Commission expires: March 12, 1987

RECEIVED  
STATE CORPORATION COMMISSION

JUL 11 1983

CONSERVATION DIVISION  
Wichita, Kansas

Vincent Oil Corporation  
125 N. Market, #1110  
Wichita, Kansas 67202

-

Omo #1  
C S/2 SW SE Sec. 35-28S-14W  
Pratt County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.  
221 S. Broadway, Suite 400  
Wichita, Kansas 67202

Commenced: June 3, 1983  
Completed: June 14, 1983

Drillers Log

Clay & Sand & Shale	240
Red Bed & Shale	1250
Shale & Shells	1865
Shale	2390
Shale & Shells	2670
Shale	2910
Shale & Lime	3495
Shale	3710
Shale & Lime	3910
Lime & Shale	4020
Lime	4680 RTD

Casing: 411' 8-5/8" cemented with 150 sacks 35-65 Pozmix Cement,  
150 sacks Class A cement, 6% Gel, 3% Calcium Chloride.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 14 1983

CONSERVATION DIVISION  
Wichita, Kansas