

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County. Sec. 35 Twp. 28S Rge. 14W EXX
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____

C - NW NW SE
Lease Owner Ronald Russ Prater, Inc.
Lease Name Omo Well No. 1

Office Address 240 N. Rock Road-Suite 235, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) 67206

Dry Hole


Date Well completed March 17, 1978
Application for plugging filed Verbal Application 19____
Application for plugging approved Verbal Approval 19____
Plugging commenced March 17, 1978
Plugging completed March 17, 1978
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,653'

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	328'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,653 ft. (rotary total depth) to 540 ft. Set plug at 540 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 540 ft. to 330 ft. Set plug at 330 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 330 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 20 sacks cement, 3 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing, Inc.
Box 169, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent (~~employee~~ of owner) of ~~XXXXXX~~
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of March, 19 78

My commission expires June 30, 1978
Elsie Willison - Notary Public.



MAR 30 1978
3-30-78
Wichita, Kansas

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Ronald Russ Prater, Inc.

SEC. 35 T. 28S R. 14W
LOC. C - NW NW SE

FARM 0110


NO. 1

COUNTY Pratt

TOTAL DEPTH 4,653'
COMM. March 5, 1978

COMP. March 17, 1978

SHOT OR TREATED
CONTRACTOR H-30, Inc.
ISSUED March 29, 1978



CASING		ELEVATION	PRODUCTION
20	10-3/4" 328' cemented w/250 sxs cement	1,980 GR.	
15	8		
12	6		
13	5		

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	278'
Red Bed and Shale	865'
Shale and Red Bed	1,651'
Shale and Lime	2,645'
Lime and Shale	3,240'
Lime	4,653'
Rotary Total Depth	4,653'


I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Suscribed and Sworn to before me a Notary Public in and for said county and state this 29th day of March, 1978.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

June 30, 1978

RECEIVED
STATE CORPORATION COMMISSION

MAR 30 1978