


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Pratt County, Sec. 35 Twp. 28 Rge. 11 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 6E $\frac{1}{2}$ NE NE
Lease Owner Imperial Oil of Kansas
Lease Name Omo Well No. #1
Office Address Wakeeney, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 1-29-62 _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1-29-62 _____ 19____
Plugging completed 2-1-62 _____ 19____
Reason for abandonment of well or producing formation dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1118 1/2 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 1150' with 1 sacks cement.
Mudded hole to 300' and sat 10' rock bridge. mixed and ran 20 sacks cement thru dump baler.
Mudded hole to 10' and sat 10' rock bridge. Mixed and dumped 10 sacks cement to base of cellar.

RECEIVED
CONSERVATION COMMISSION
FEB 5 1962
2-5-62
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2 day of February, 19 62

My commission expires 24 October 1964
Sidney D. Miller
Notary Public.



DRILLER'S LOG

Imperial Oil Company
780 Fourth National Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1962
CONSERVATION DIVISION
Wichita, Kansas

Omo No. 1
C E 1/2 NE NE Sec. ~~26-28S-11W~~
Pratt County, Kansas

Total Depth: 4507

Commenced: 10-18-61 Completed: 11-7-61

Elevation: 1983 K.B.
Production:

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" surface pipe at 820' with 325 sacks cement.
Set 4-1/2" production casing at 4506' with 125 sacks cement.

Figures indicate bottom of formations:

		<u>TOPS</u>	(Spl.)
Shale & Shells	208'	Heebner	3774 (-1779)
Shale & Sand	810'	Brown Lime	3954 (-1971)
Shale & Shells	1965'	Lansing	3972 (-1989)
Shale & Lime	3515'	Base Kansas City	4332 (-2349)
Lime & Shale	3995'	Marmaton	4349 (-2366)
Lime	4470'	Conglomerate Chert	4424 (-2441)
Lime & Chert	4495'	Viola	4442 (-2459)
Lime & Shale	4507'	Simpson Shale	4500 (-2517)
Rotary Total Depth	4507'	Simpson Sand	4504 (-2521)
		Rotary Total Depth	4507 (-2524)

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.


IMPERIAL OIL COMPANY


Raymond L. Bacon

Subscribed and sworn to before me this 10th day of November, 1961.

My Commission Expires:

July 27, 1964


Bette J. Behymer, Notary Public