


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Kiowa County. Sec. 16 Twp. 29S Rge. (E) 16 (W)
Location as "NE/CNW/SW" or footage from lines C-SW SW NE



Locate well correctly on above
Section Plat

Lease Owner Gulf Oil Corporation
Lease Name Clara Pyle Well No. 2
Office Address Box 661, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 7-17 19 55
Application for plugging filed 6-18 19 56
Application for plugging approved 6-19 19 56
Plugging commenced 7-6 19 56
Plugging completed 7-15 19 56
Reason for abandonment of well or producing formation Well producing no oil.

If a producing well is abandoned, date of last production 10-25 19 55
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Mississippi Depth to top 4686' Bottom 4740' Total Depth of Well 4740 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	361'	-0-
				5-1/2"	4769'	3599'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand to 4670' and capped with 5 sx cement. Filled hole with mud to 350' of surface, set rock bridge and capped with 20 sx cement. Mudded hole to 35' of surface set rock bridge and capped with 10 sx cement. Filling hole into cellar

RECEIVED
STATE CORPORATION COMMISSION
JUL 21 1956
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
R. G. Bachtell (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. G. Bachtell
Box 225, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17 day of July, 19 56

My commission expires October 26, 1959

R. Brown
Notary Public.

:BNG
7-16-56

PLUGGING
FILE SEC. 16 T. 29 R. 16w
BOOK PAGE 72 LINE 18

WELL RECORD

GULF T 880-A PRINTED IN U.S.A.

WELL NO. 2 LEASE Clara Fyle COMPANY Gulf Oil Corporation and Falcon Seaboard A.F.E. 6228
 DATE—DRILLING BEGAN 6-23-55 WELL COMPLETED 7-18-55 FIRST PRODUCTION 7-17-55
 SAND RECORD MISSISSIPPIAN: (Perf. 4699-4711') TOTAL DEPTH 4770'

INITIAL PRODUCTION Oil: "P" 120 barrels - based on pumping 40 bbl.
 Water: 0 barrels oil on 8 hr. State test.

CASING RECORD

SIZE	WEIGHT	THD.	CLASS	MAKE	SET AT DEPTH	SACKS CEMENT	LBS. GAL. CHLO.	PULLED	LEFT IN
8-5/8	"	"	"	"	361	375			361
5-1/2	14	8R	A	GS	4769	100			4769
* 2 jts. 33#, 8V, C-1, LM 7 jts. 23#, Armer Slip joint 1 jt. 32, 8R, C-1, LM Distance 4 - 11' from PK to top of 5/8" casing.									

S- 16 T- 298 R- 16W

CENTER									
GW									
GW									
WB									
STATE									
COUNTY									
TOWNSHIP									

ELEVATION—

Perf. Miss. 4699-4711 w/4 slots per foot. Treated with 250 gallons mud acid.

FORMATION RECORD

Surface Soil & Gravel	0	40	Lime	4315
Gravel		134	Lime & Shale	4407
Sand & Red Bed		370	Lime	4491
Shale, Red Bed & Sand		1070	Lime & Shale	4685
Red. Bed & Sand		1605	Core No. 1	4689
Shale & Shells		2040	Core No. 2	4691
Shale & Lime		2323	Chert	4696
Lime		2502	Lime & Chert	4720
Lime & Shale		3627	Lime & Shale	4748
Lime, Shale & Sand		3769	Shale & Chert	4766
Lime & Shale		4009	Lime	4770
Lime, Shale & Sand		4145	Total Depth	4770

RECEIVED
 STATE CORPORATION COMMISSION

JUN 19 1956

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 16 T 29 R 16W
 BOOK PAGE 72 LINE 18

