

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

KIOWA County. Sec. 20 Twp. 29S Rge. (E) 16 (W)  
Location as "NE/CNW/SW" or footage from lines C NE SE

Lease Owner PAN WESTERN PETROLEUM, INC.  
Lease Name McCLURE Well No. 1  
Office Address 404 ONE TWENTY BLDG., WICHITA, KANSAS 67202  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed MAY 13, 19 67  
Application for plugging filed (PHONE 5/13/67) MAY 18, 19 67  
Application for plugging approved MAY 13, 19 67  
Plugging commenced MAY 13, 19 67  
Plugging completed MAY 13, 19 67  
Reason for abandonment of well or producing formation



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING  
Producing formation Depth to top Bottom Total Depth of Well 4783 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	270	8-5/8	270	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 240 FEET. SET FIRST PLUG AT 240 FEET WITH 1/2 SACK HULLS AND 25 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET SECOND PLUG WITH 1/2 SACK HULLS AND 10 SACKS CEMENT. PLUGGED RAT HOLE WITH 2 SACKS CEMENT. JOB COMPLETE AT 3:15 AM ON MAY 13, 1967.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 24 1967

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES, INC.  
Address 830 SUTTON PLACE, WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
E. E. HALL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall

830 SUTTON PLACE, WICHITA, KANSAS 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 18TH day of MAY, 19 67

My commission expires FEB. 1, 1968

Barbara J. Layton  
BARBARA J. LAYTON Notary Public.

GABBERT JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

MC CLURE #1  
 C NE SE SECTION 20-29S-16W  
 KIOWA COUNTY, KANSAS

COMMENCED: MAY 2, 1967  
 COMPLETED: MAY 13, 1967

OPERATOR - PAN WESTERN PETROLEUM, INC.

DEPTH		FORMATION	REMARKS
FROM	TO		
0	85	CLAY	
85	98	SAND	
98	270	SHALE	RAN 12 JOINTS OF 8-5/8" CASING, SET @ 270' w/225 SACKS CEMENT.
270	1087	SHALE AND SHELLS	
1087	1365	RED BED	
1365	1940	SHALE, SHELLS AND LIME	
1940	2110	SHALE AND LIME	
2110	2300	LIME	
2300	3095	LIME AND SHALE	
3095	3240	SHALE	
3240	3500	LIME AND SHALE	
3500	3686	LIME	
3686	4075	LIME AND SHALE	
4075	4510	LIME	
4510	4629	LIME AND SHALE	
4629	4633	SHALE	
4633	4714	LIME	
4714	4743	CHERT AND LIME	
4743	4783	LIME	
4783	TD		DRY AND ABANDONED.

**RECEIVED**  
 STATE CORPORATION COMMISSION

MAY 24 1967

CONSERVATION DIVISION  
 Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C NE SE SECTION 20-29S-16W, KIOWA COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

*E. E. Hall*

E. E. HALL

STATE OF KANSAS )  
 ) SS.  
 COUNTY OF SEDGWICK )

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 17TH DAY OF MAY, 1967, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

*Barbara J. Layton*

BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1968.