

LEASE NAME Miller

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

1650 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 31 TWP. 25 RGE. 8 ~~XXXX~~ (W)

COUNTY Reno

Date Well Completed N/A

Plugging Commenced 11-15-96

Plugging Completed 11-19-96

LEASE OPERATOR Mach Petroleum Inc.

ADDRESS P.O. Box 35583, Tulsa, OK 74153

PHONE#(316) 596-2676 OPERATORS LICENSE NO. 30146

Character of Well Good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-15-96 (date)

by Jack Luthie (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? yes

Producing Formation N/A Depth to Top 3902 Bottom 3922 T.D. 4390

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	302	None
				5 1/2	4410	2850

Describe in detail the manner in which the well was plugged, indicating when the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s
Set CIBP at 3850, dump 2sx portland cement with dump bailer, stretch and cut pipe at 2850,
pull casing to 1329 and spot 35sx, pull casing to 765 and spot 35sx, pull casing to 319 and
circulate cement to surface, all common cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mach Petroleum Inc.

STATE OF Kansas COUNTY OF Barber, ss.

Alan Vratil (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fac
statements, and matters herein contained and the log of the above-described well as filed t
the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Medicine Lodge, KS 67104



SUBSCRIBED AND SWORN TO before me this 25 day of November, 1996

Glenda Morrison
Notary Public

My Commission Expires: 10-14-98