

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Kingman County, Sec. 16 Twp. 27S Rge. 7 (E) W (W)

Location as "NE/CNW&SW" or footage from lines NE/4 SW/4 SE/4

Lease Owner Heathman-Seeligson Drilling Co.

Lease Name Wooldridge "B" Well No. 1

Office Address 1015 East Second, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-24-1955

Application for plugging filed 3-24-1955

Application for plugging approved 3-24-1955

Plugging commenced 3-24-1955

Plugging completed 3-24-1955

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee, McPherson, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3885 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE                 | PUT IN | PULLED OUT |
|-----------|---------|------|----|----------------------|--------|------------|
|           |         |      |    | 6 jts. 8-5/8" new    |        |            |
|           |         |      |    | csg. set at 192'     |        |            |
|           |         |      |    | cemented w/115 sacks |        |            |
|           |         |      |    | cement & 2 Calcium   |        |            |
|           |         |      |    | Chloride             |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Stirred pits. Build mud up to 12#. Filled hole to 170' - set plug with 15 sacks cement thru drill pipe. Filled hole to 25' - set plug with 1/2 sacks hulls & 5 sacks cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Heathman-Seeligson Drilling Co.

Address 1015 East Second, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. H. D. Shreve (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) By: [Signature]

1015 East Second, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25 day of March, 1955

My commission expires June 28, 1956

[Signature] Notary Public.

PLUGGING FILE SEC 16 T 27 S 7W BOOK PAGE 107 JUNE 8

3-30-1955

DRILLERS' LOG

NAME: WOOLDRIDGE "B" #1 DATE SPUDDED: 3-12-55  
LOCATION: NE/4 SW/4 SE/4 Sec. 16-27S-7W ROTARY COMPLETED: 3-24-55  
Kingman County, Kansas  
OPERATOR: Heathman-Seeligson Drilling Co. ELEVATION: 1545 GR  
1547 DF  
1550 KB  
CONTRACTOR: Heathman-Seeligson Drilling Co. ROTARY TOTAL DEPTH: 3885'  
CASING RECORD: 6 jts. 8-5/8" new casing set at  
192' cemented w/115 sacks cement  
and 2 Calcium Chloride. Cement  
Circulated.  
OIL STRING: None run - Dry and abandoned 3-24-55

GEOLOGICAL TOPS (KB)

|               |              |
|---------------|--------------|
| Brown Lime    | 3129 (-1579) |
| Lansing       | 3145 (-1595) |
| Mississippian | 3851 (-2301) |
| R.T.D.        | 3885'        |

LOG

(Figures indicate bottom of formation)


|                    |          |
|--------------------|----------|
| Shale & Rock       | 0 to 140 |
| Sand               | 165      |
| Shale & Shells     | 190      |
| Red Bed & Sand     | 475      |
| Shale & Shells     | 700      |
| Salt               | 1015     |
| Lime & Shale       | 2620     |
| Lime               | 2635     |
| Lime & Shale       | 2908     |
| Lime, Shale & Sand | 3115     |
| Lime & Shale       | 3370     |
| Lime               | 3715     |
| Lime & Shale       | 3840     |
| Shale              | 3851     |
| Lime               | 3855     |
| Chat               | 3885     |
| R.T.D.             | 3885'    |

The undersigned, H. D. Shreve, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

HEATHMAN-SEELIGSON DRILLING CO.

By: 

Subscribed and sworn to before me  
this 25th day of March, 1955.

  
Notary Public

My Commission expires: June 28, 1956

