

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission

P. O. BOX 17027  
Wichita, Kansas 67217

WELL PLUGGING RECORD

Sedgwick County, Sec 31 Twp. 27 Rge. 4W (E) (W)

Location as "NE/CN/SE/SW" or footage from lines E/2 NW4

Lease Owner Maurice L. Brown

Lease Name Bartholomew Tract 9; Well #1 Well No.

Office Address Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 5/10/74 19

Plugging completed 5/15/74 19

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dewey

Producing formation Depth to top Bottom Total Depth of Well 3725 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	196	none
				5 1/2"	3710	3307'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded to 3700' and set 5 sacks cement. Shot pipe at 3406', 3304', pulled 104 joints. Set rock bridge at 250' and ran 5 yards ready mix. Tallied pipe.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 28 1974

5-28-1974

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor (If additional description is necessary, use BACK of this sheet)

Address VOTH CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE  
WALTER VOTH ss.

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth  
CHASE, KANSAS

Subscribed and Sworn to before me this 24th day of May 1974

MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

Margaret Melcher  
Notary Public.

D R I L L E R S   L O G

COMPANY: Huber & Pabco  
 CONTRACTOR: Pabco Drilling, Inc.

LOCATION: E/2 NW/4  
 31-27-4W  
 Sedgwick Co.

FARM NAME: No. 1 Lorenz

PRODUCTION:

COMMENCEC: 2-11-50

COMPLETED: 3-1 -50

CASING USED:

8 5/8"	196'	cem w 150 sx
5 1/2"	3735'	cem w 75 sx

Shale, Sand & Shells	186
Cement	196
Shale & Shells	238
Shale & Shells	286
Shale & Shells	665
Sand	675
Shale & Lime	750
Shale & Lime	910
Shale & Lime	1070
Lime & Shale	1285
Lime & Shale	1420
Lime & Shale	1550
Shale & Lime	1732
Shale & Shells	1965
Shale & Shells	2150
Shale & Lime	2305
Shale & Lime	2400
Lime & Shale	2560
Lime & Shale	2655
Lime & Shale	2755
Shale & Lime	2845
Lime	2885
Lime	2950
Lime	2981
Lime	3044
Lime	3110
Lime	3155
Lime	3212
Lime	3252
Lime	3303
Lime	3307
Lime & Shale	3370
Shale & Lime	3405
Shale & Lime	3485
Shale & Lime	3540
Lime & Shale	3598
Lime & Shale	3657
Shale & Lime	3715
Lime	3735
Total Depth	3735

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 15 1974  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 COUNTY OF SEDGWICK ) SS

I, D. J. Briggs, hereby certify that the above is a true and correct copy of the log on the No. 1 Lorenz, located in the East Half of the Northwest Quarter (E/2 NW/4) of Seciton 31, Township 27 South, Range 4 West, Sedgwick County, Kansas.

D. J. Briggs  
 D. J. Briggs, Secy Treas

Subscribed and sworn to before me this 20 day of March, 1950

My commission expires March 2, 1953

Ruth M. Gardner  
 Notary Public