

R


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Sedgwick County. Sec. 31 Twp. 27 Rge. 4 ~~(E)~~ ^W (W)

Location as "NE/CNW/SW" or footage from lines. NE SE NW
Lease Owner Shallow Water Refining Company
Lease Name Bartholmew TR9 Well No. 4
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced BXX 9/13/67 _____ 19____
Plugging completed 9/16/67 _____ 19____
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3744 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	195'	none
				5-1/2"	3733'	3371'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, checked sand and set 5 sacks of cement. Loaded hole with water. Shot pipe at 3377', worked pipe loose. Mudded hole to 370', set 20' rock bridge and plugged hole with 6 yards of ready mix. Tallied pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1967
9-21-1967
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of September, 19 67

My commission expires February 15, 1971

[Signature]
Notary Public.

Sheet 924
Q

Company - HUBER, BRIGGS, FLOOD, CLICKER
Farm - Lorenz No. 4

SEC. 31 T. 27 R. 17
NE SE NW

Total Depth. 3742
Comm. 4-22-50 Comp. 5-3-50
Shot or Treater.
Contractor. Pablo Drilling,
Issued. 6-3-50

County. Southwick
KANSAS



LOGGING:
8 5/8" 200' cem. w/150 sx.
5 1/2" 275' cem. /50 sx.

Elevation. _____

Production. B.P.B. 1022

Figures Indicate Bottom of Formations

surface clay	60
shale sdy	110
shale & shells	350
shale	625
silt	750
shale shells	875
shale sdy	1015
lim. & shale	1260
lime	1565
shale	2035
shale & lime	2970
lime	3534
lime & shale	3730
Miss chat RTE	3737
chat	3742
Total Depth	
Tops:	
Lansing	2872
Miss.	3686
dolo.	3732

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1967

CONSERVATION DIVISION
WICHITA, KANSAS