

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Sedgwick County. Sec. 31 Twp. 27 Rge. 4 W(E) (W)

Location as "NE/CNW/SW" or footage from lines NE NW SE

Lease Owner Shallow Water Refining Company

Lease Name Bartholomew Tract 15 #3W Well No. _____

Office Address Kansas City, Missouri 64112

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19____

Application for plugging filed _____ 19____

Application for plugging approved _____ 19____

Plugging commenced 12/20/68 _____ 19____

Plugging completed 12/24/68 _____ 19____

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dewey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3732 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	191'	none
				5 1/2"	3717'	1316'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, pushed plug to 2300', ran 50' of sand and 4 sacks of cement. Loaded surface and casing, cut off braden head and welded on 8-5/8" collar. Put stripper head on and rigged up on 5 1/2" casing. Checked hole, shot pipe at 1715', 1610', 1501', 1411', 1316', worked pipe loose and pulled 43 joints of 5 1/2". Bailed hole to 220', 20' rock bridge and filled hole with 4 yards ready mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

JAN 7 1969

CONSERVATION DIVISION
Wichita, Kansas

1-7-1969

(If additional description is necessary, use BACK of this sheet)
KNIGHT CASING PULLING CO., INC.

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.

Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Noel Knight
CHASE, KANSAS

(Address)

Subscribed and Sworn to before me this 30th day of December, 1968

My commission expires February 15, 1971

Margaret Melcher
Notary Public.



Sheet 15

R

KANSAS LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK • WICHITA, KANSAS

COMPANY L. B. STABLE FORD

SEC. 31 T. 27 R. 4W

FARM Dieffenbacher NO. 3


LOC. NE NW SE

TOTAL DEPTH 3732

COUNTY Sedgwick
KANSAS

COMM. 1-21-51

COMP. 2-4-51



SHOT OR TREATED

CONTRACTOR

ISSUED 4-28-51

CASINO

8 5/8" 191' cem. w/150 sx
5 1/2" 3717' cem. w/100 sx

ELEVATION

PRODUCTION I.P.P. 215 BO
& 4% wtr

FIGURES INDICATE BOTTOM OF FORMATIONS

surface clay & red rock	25
sand, shale & shells	120
shale & shells	750
shale & lime shells	875
shale & lime	1380
shale, shells	2350
lime & shale	2460
shale shells	2665
shale & lime	2830
shale & shells	2883
lime	2935
shale & lime	3005
lime	3090
shale & lime	3165
lime	3260
shale & lime	3685
lime	3732
Total Depth	
Scout Tops:	
Lansing	2876
Miss. Lime	3886

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1968
CONSERVATION DIVISION
Wichita, Kansas