

R


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Sedgwick County, Sec. 31 Twp. 27 Rge. 4 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NE NW
Lease Owner Shallow Water Refining Company
Lease Name Bartholmew TR9 Well No. 3
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9/6/67 19
Plugging completed 9/9/67 19
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Justice
Producing formation Depth to top Bottom Total Depth of Well 3746 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13"	145'	none
				5 1/2"	3721'	2816'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded hole to 3700', set 5 sacks of cement.
Shot pipe at 2884', 2821', worked pipe loose. Well started to gas, bled off 40 bbl. oil. Mudded hole to 220', set 20' rock bridge and plugged with 5 yards of ready mix. Tallied pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSIONS
SEP 18 1967
SEP 18 1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of September, 19 67

My commission expires February 15, 1971

[Signature] Notary Public.

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas


Sheet 9 # 3
67

Company - HUBER, BRIGGS, BLOOD & CLICKNER
Farm - Lorenz No. 3

SEC. 31 T. 27 S. LW
SW NE NW

Total Depth. 3746
Comm. 4-1-50 Comp. 4-14-50
Shot or Treated.
Contractor. Pabco Drlg. Co.
Issued. 6-3-50

County, Sedgwick
KANSAS



CASING:
13" 150' com. w/135 sx.
5 1/2" 3730' com. w/125 sx.

Elevation. _____

Production. B. H. B. 693 / 6%

Figures Indicate Bottom of Formations.

surface clay	35
shale & shells	118
sand & shale	130
shale & snells	560
shale & salt	645
shale & shells	685
shale, shells, & lime	910
shale & lime	1420
shale	1485
lime & shale	1690
shale	1850
shale & lime	2700
lime	2745
shale & lime	2845
lime	2987
K.C. lime	3043
lime	3315
shale & lime	3362
lime	3513
shale & lime	3720
lime	3746
Total Depth	

Tops:	
T. Brown lime	2827
Lansing	2865
Mississippi	3687
Dclomite	3719

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1967

ELEVATION DIVISION
Wichita, Kansas