

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-097-21,421-2000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Pickrell Drilling Company, Inc. KCC LICENSE # 5123  
(owner/company name) (operator's)

ADDRESS 110 N. Market, Suite 205 CITY Wichita,

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-8427

LEASE Smith "VB" WELL# 3 SEC. 34 T. 29S R. 19 (East ~~West~~)

W/2 SW - SW SPOT LOCATION/QQQQ COUNTY Kiowa

660 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM N/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 570'KB CEMENTED WITH 300sx SACKS

PRODUCTION CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: None

ELEVATION 2291 / 2296 T.D. 5200' PBTD \_\_\_\_\_ ANHYDRITE DEPTH 1218(+1078)  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING P&A as follows: 50sx @ 1220', 50sx @ 600', 40sx @ 275', 10sx @ 40', 15sx in rathole (total 165sx) of 60-40 poz, 6% gel. Complete @ 10:30 AM on 2-22-97.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Doyle Folkerts PHONE# (316) 793-5742

ADDRESS P.O. Box 1303 City/State Great Bend, Kansas 67530

PLUGGING CONTRACTOR Pickrell Drilling Co. Inc. KCC LICENSE # 5123

ADDRESS 110 N. Market, Suite 205 - Wichita, KS. (company name) (contractor's)  
PHONE # (316) 262-8427

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Completed @ 10:30 AM on 2-22-97.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3-10-97 AUTHORIZED OPERATOR/AGENT: C. W. Sebts

(Signature)  
C. W. Sebts - President

RECEIVED  
KANSAS CORP COM  
MAR 11 1997