



KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
JAN 16 1967  
1-16-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name National Associated Petroleum Company

Complete Address: Fifth Floor, Ritz Bldg., Tulsa, Oklahoma

Lease Name Elsie Omo Well No. # 1-A

Location App. SE SE NE Sec. 35 Twp. 28 Rge. 14 (E) (W) W

County Pratt Total Depth 4646'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Red Tiger Drilling Company

Address: 1720 Wichita Plaza Bldg., Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 5:15PM Day 14th Month Jan. Year 1967

The Above well was plugged as follows:

308' of 8 5/8" surface pipe, cement circulated with 250 sacks. Hole  
was filled with drilling mud to 300', 1st cementing plug, bridged with  
2 sacks of dry cement and 1/2 sack of hulls on fluid at 300', and cemented  
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at  
40', and cemented with 9 sacks to the base of the cellar. Rat hole bridged  
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-16-67

INV. NO. 4609-W

Signed: Aubie Elving  
Well Plugging Supervisor