

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1967

CONSERVATION DIVISION
Wichita, Kansas

5-15-1967

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed April 25, 1967.

Operator's Full Name Pan-Western Petroleum, Inc.

Complete Address: 404 One Twenty Bldg., Wichita, Kansas 67202

Lease Name McClure-Breidenthal Well No. # 1

Location C NE SE Sec. 20 Twp. 29 Rge. 16 (E) (W) W

County Kiowa Total Depth 4783'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Gabbert-Jones, Inc.

Address: 830 Sutton Place, Wichita, Kansas License No.

Operation Completed: Hour 3:15AM Day 13th Month May Year 1967

The Above well was plugged as follows:

270' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole
was filled with drilling mud to 240', 1st cementing plug, bridged with
2 sacks of dry cement and 1/2 sack of hulls on fluid at 240', and cemented
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at
40', and cemented with 9 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/15/67
INV. NO. 5220-W