

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 2 - 1964

CONSERVATION DIVISION  
Wichita, Kansas

10-2-1964

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Apache Corporation

Complete Address: 823 South Detroit, Tulsa, Oklahoma

Lease Name Wedel Well No. # 1

Location NW SW Sec. 1 Twp. 29 Rge. 18 (E) (W) W

County Kiowa Total Depth 4964

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 12:30PM Day 1st Month Oct. Year 1964

The Above well was plugged as follows:

348' of 8 5/8" surface pipe, cemented with 300 sacks. 4960' of 4 1/2" long string, cemented with 100 sacks. Plug back to 4900'. Top perforation 4874'. Bottom of the hole was squeezed with 20 sacks cement, cement and plug was pumped with water to 4733'. Water was up in the hole at 240'. Bridge plug was pushed in fluid to 325', and 5' of rock bridge. 2 sacks of cement was mixed in barrel and put on plug, through dump bailer at 320', and let set over-night. Next morning water in hole was bailed dry; and 33 sacks of cement was added to plug. Hole was filled with mud to 40', and 10' of rock bridge, and cemented with 10 sacks to the base of the cellar. 4236' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

DATE 10/2/64

Signed: Archie Elvins  
Well Plugging Supervisor

INV. NO. 9906-U