

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 11 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name James F. Smith 3-11-1964

Complete Address: Box 10005, Amarillo, Texas

Lease Name Conklin Well No. # 1-9

Location C NE NE Sec. 9 Twp. 29 Rge. 17 (E) (W) W

County Kiowa Total Depth 4834

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Tommy Ward Drilling Co.

Address: 609 Liberty Bank Bldg., Oklahoma City, Okla. License No. _____

Operation Completed: Hour 1:00PM Day 10th Month March Year 1964

The Above well was plugged as follows:

420' of 8 5/8" surface pipe, cemented with 275 sacks. Hole was filled
with drilling mud to 340', 1st cementing plug, bridged solid with hulls
at 340', and cemented with 25 sacks. Hole was filled with drilling mud
to 40', 2nd cementing plug, bridged solid with hulls at 40', and cement-
ed with 10 sacks to base cellar. Rat and mouse hole bridged and cemented
with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 3/11/64

INV. NO. 8441-W