

KANSAS  
STATE CORPORATION COMMISSION

*Q*

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 104-1 County: Pratt

Location: SW SE NW Sec. 13 Twp. 29 Rge. 13 (E) (W) X

Name of Field: \_\_\_\_\_ Total Depth: 4745

I have this date completed supervision of plugging of:

Lease Name: Thompson Well No. 1

Operator's Full Name: The Texas Co.

Complete Address: 614 Bitting Bldg, Wichita, Kans.

Plugging Contractor: Glenn & Smith

Address: Ellenwood, Kans. License No. \_\_\_\_\_

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No X

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 4 PM Day 21 Month August Year 19 58

The above well was plugged as follows:

240' of 13 3/8" surface casing circulated with cement. 933' of 9 5/8"  
casing with 500 sack cement behind pipe. Heavy drilling mud pumped to  
930' with cementing plug and 25 sack cement from 830' to 870'. Heavy  
mud to 240' with rock bridge to 230' and 35 sack cement top bridge.  
Heavy mud to 35' with 10 rock bridge and cement to base of cellar.

Signed: *W. H. King*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC. 13 T. 29 R. 13  
BOOK PAGE 104 LINE 1

STATE CORPORATION COMMISSION  
AUG 29 1958

8-29-1958