

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 19 1965

CONSERVATION DIVISION  
Wichita, Kansas

7-19-1965

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Solar Oil Company

Complete Address: 1117 Union National Bldg., Wichita, Kansas

Lease Name Graber Well No. # 1

Location C NW SW Sec. 34 Twp. 27 Rge. 7 (E) (W) W

County Kingman Total Depth 4320'  
4420'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: S & S Drilling Company

Address: Box 24, Great Bend, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 3:00 PM Day 16th Month July Year 1965

The Above well was plugged as follows:

259' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole  
was filled with drilling mud to 250', 1st cementing plug, bridged solid  
with dry cement and hulls on fluid at 250', and cemented with 25 sacks.  
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged  
solid with dry cement and hulls on fluid at 40', and cemented with 10  
sacks to the base of the cellar. Rat hole bridged and cemented with 2  
sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 7/20/65  
INV. NO. 1474-4