

KANSAS

SC
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 18 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill;
filed August 29, 1967.

Operator's Full Name Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas 67202

Lease Name Dickerson Well No. # 1

Location C NE SW Sec. 20 Twp. 27 Rge. 7 (E) (W) W

County Kingman Total Depth 4350'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Mack Oil Company

Address: 812 Union Center Bldg., Wichita, Ks. 67202 License No. _____

Operation Completed: Hour 1:30PM Day 15th Month Sept. Year 1967

The Above well was plugged as follows:

270' of 8 5/8" surface pipe, cement circulated with 250 sacks. Hole was
filled with drilling mud to 260', 1st cementing plug, bridged with 1/2 sack of
Gel-Mud and 1/2 sack of hulls on fluid at 260', and cemented with 30 sacks, through
the drill pipe, with cement from 250' to 160'. Hole was filled with drilling mud
to 60', 2nd cementing plug, bridged with 1/2 sack of Gel-Mud and 1/4 sack of hulls
on fluid at 60', and cemented with 25 sacks, with cement from 60' to the base
of the cellar. Rat and mouse holes bridged and cemented with 5 sacks.

This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlene Elving
Well Plugging Supervisor

DATE 9/18/67
INV. NO. 6352-U