

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority: Dec. 10/68
Well Plugging Completed: Jan. 13/69

Operator's Full Name The Shallow Water Refg. Co. 1500 Wichita Plaza Wichita, Ks.
Complete Address: % The Shallow Water Refg. Co. Box 11320 Kansas City, Mo. 64112

Lease Name Bartholomew Unit Tct. #10 Well No. 2

Location NW NW NE Sec. 31 Twp. 27 Rge. 4W (E) (W)

County Sedgwick Total Depth 3746'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Plg. Co.

Address: Box 405 Chase, Kans. License No. 436

Operation Completed: Hour Day 13/6 Month Jan. Year 1969

The Above well was plugged as follows:

T.D. - 3746'.

3705' - 5 1/2", plugged back to 3428'.

Perforated 3226' - pushed plug to 3230'. Sand to 3210' - 4 sacks cement.

2840' - 5 1/2" recovered.

330' - 10" surface pipe.

Bridge 350' - 330', 5 yds. Redi-mix with 2% CC to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ted E. Hawley
Well Plugging Supervisor

DATE 1-20-69

INV. NO. 9184-E