

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill, filed
February 24, 1967.

RECORDED
MAR 8 1967
3-8-67
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Thunderbird Drilling, Inc.

Complete Address: 400 North Woodlawn, Suite 7, Wichita, Kansas

Lease Name Wilkinson Well No. # 1

Location C NE NE Sec. 8 Twp. 27 Rge. 6 (E) W

County Kingman Total Depth 4083'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Gabbert-Jones, Inc.

Address: 830 Sutton Place, Wichita, Kansas License No.

Operation Completed: Hour 2:15PM Day 6th Month March Year 1967

The Above well was plugged as follows:

267' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole
was filled with drilling mud to 260', bridged with 2 sacks of dry cement
and 1/2 sack of hulls on fluid at 260', and cemented with 23 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged with 1
sack of dry cement and 1/2 sack of hulls on fluid at 40', and cemented with
9 sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/8/67
INV. NO. 4899-W

Signed: Audie Elving
Well Plugging Supervisor