

69P

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 2 1966

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Shallow Waters Ref. Co. 1325 Wichita Plaza  
Complete Address: c/o P.O. Box - 11320 - Kansas City, Mo. (64113)  
Lease Name Banholman Unit, Tract 14 Well No. 6  
Location SE-NE-SW Sec. 31 Twp. 27 Rge. (E) 4(W)  
County Sedgewick Total Depth 3754  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling Co.  
Address: Chase, Kansas License No. 436

Operation Completed: Hour 2:00 <sup>PM</sup> Day 1 Month 3 Year 1966

The Above well was plugged as follows:

Filled hole with sands to 3740 ft.  
Mixed and dumped 5 sacks cement.  
Pulled 3110 ft. 5 1/2" casing.  
Set a 15 ft. Rock Bridge from 205 ft.  
to 190 ft. Added 20 sacks cement.  
Mudded hole from this point to 35 ft.  
Added 10 sacks of cement to surface.  
(202 ft. of 8 5/8" surface pipe cemented with 135 sacks of cement.)

I hereby certify that the above well was plugged as herein stated.

Signed: Paul Amick  
Well Plugging Supervisor

Woth

INVOICED

DATE 3-2-66

INV. NO. 3091-E