

*SPR*

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

JAN 19 1966

CONSERVATION DIVISION  
Wichita, Kansas  
*Wichita, Kas.*

Operator's Full Name Shallow Water Ref. Co. 1325 - Wichita Plaza  
Complete Address: c/o Shallow Water Ref. Co. Box 11320, Kansas City, Mo.  
Lease Name Basement Unit Tract of Well No. 3  
Location NW-NE-SW- Sec. 31 Twp. 29 Rge. 4 W (W)  
County ~~Butler~~ Sedgwick Total Depth 3744  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Royce Loring Pullinger

Address: Chase Hans License No. 436

Operation Completed: Hour 8:45 Day 18 Month 1 Year 1966

The Above well was plugged as follows:

Filled Hole with sand to 3720 ft.  
Mixed & dumped 5 sacks cement.  
Pulled 2264 ft. of 5" casing.  
Set a 15 ft. Rock Bridge at 200 ft.  
Added 20 sacks cement. Mudded  
hole from this point to 35 ft. added 10 ft. of  
Rock - Then 10 sacks cement to surface.  
(215' of 10" surface Pipe - cemented with 135 sacks.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Paul Empson  
Well Plugging Supervisor

DATE 1-19-66  
INV. NO. 2864-E