

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 27 1965
12-27-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Shallow-Water Refg - 1325 - Wichita Plaza - Wichita, Ks.

Complete Address: C/o Shallow-Water Refg - Box 1325 - Kans. City, Mo. (64112)

Lease Name Bartholomew Unit Tract 14 Well No. 4

Location NW-SW-SW- Sec. 31 Twp. 27 Rge. (E) 4(W)

County Sedgewick Total Depth 3775

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Co. Inc.

Address: Chase Road License No. 436

Operation Completed: Hour 6:00 Day 22 Month 12 Year 1965

The Above well was plugged as follows:

Gilled hole with sand to 3760 ft.
Mixed & dumped 5 sacks cement.
Pulled 3312 ft. of 5 1/2" casing.
Set a 15 ft. Rock Bridge at 200 ft.
Added 20 sacks of cement.
Mudded hole from this point to 30 ft.
added 10 sacks of cement to mudline.
(203 ft. of 8 1/2" surface pipe cemented with 135 sacks
Cement.)

I hereby certify that the above well was plugged as herein stated.

INVOICED
Walter
DATE 12/28/65

Signed: Paul
Well Plugging Supervisor