

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUN 12 1963

CONSERVATION DIV.
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Meade of J. M. Huber Corporation has this date requested permission to plug the following described well:

Mr. Meade guarantees payment of the plugging fee.

Operator's full Name: J. M. Hiber Corporation

Complete Address: 5415 Pennsylvania, Oklahoma City, Okla.

Lease Name: Hammond Well No. # 1

Location: G SW NW Sec. 21 Twp. 29 Rge. 17 (E) (W)W

County Kiowa Total Depth 4990 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Meade was instructed to plug the well as follows:

411' of 8 5/8" surface pipe, cement circulated with 325
sacks. Fill hole with mud to 240', 1st cementing plug,
1/2 sack hulls, cement with 20 sacks. Fill hole with mud
to 40', 2nd cementing plug, 1/2 sack hulls, cement with 10
sacks to base cellar. Bridge and cement rat hole with 2
sacks.

Very truly yours,

Audie Elving
 Conservation Division Agent