

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 5 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Damme of Red Tiger Drlg Co has this

date requested permission to plug the following described well:

Mr. Damme guarantees payment of the plugging fee.

Operator's full Name: Patton Oil Co

Complete Address: 70 W 6th Ave Denver, CO

Lease Name: Horney B Well No. 1

Location: NE/NE Sec. 19 Twp. 29S Rge. 17 (E)(W) W

County: Kiowa Total Depth 4937 Oil Well

Gas Well Input Well SWD Well D & A ~~Cost~~ ~~hole~~ ~~down~~ Wash-

Mr. Damme was instructed to plug the well as follows:

334 ft 8 5/8 surface cemented with 180 sacks. Fill hole

to 300 ft, plug, 1/2 sack hulls, 40 sacks cement. Mud to

40 ft, plug, 1/2 sack hulls, 15 sacks cement to surface.

2 sacks cement in rat hole.

Very truly yours,

Russell Bickert
Conservation Division Agent