

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 18 1964

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Bill Musgrove of Bowers Drilling Co., Inc has this  
 date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Jas. F. Smith

Complete Address: P. O. Box 10005, Amarillo, Texas

Lease Name: Robbins Well No. # 1-27

Location: C SW NE Sec. 27 Twp. 29 Rge. 17 (E) (W) W

County Kiowa Total Depth 4804 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

376' of 8 5/8" surface pipe, cemented with 375 sacks. Fill  
hole with drilling mud to 275', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drill-  
ing mud to 40', 2nd cementing plug, bridge with hulls, and  
cement with 10 sacks to base cellar. Bridge and cement rat  
hole with 2 sacks.

Very truly yours,

Achie Elving  
 Conservation Division Agent