

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 19 1967  
5-15-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed April 26, 1967

Dear Sir:

Mr. Otto Beren of Donelson Drilling Company as this  
date requested permission to plug the following described well:

Mr. Beren guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Compant, Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name: Morris Well No. # 1

Location: C SW SE Sec. 6 Twp. 29 Rge. 19 (E)(W) W

County Kiowa Total Depth 5155' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Beren was instructed to plug the well as follows:

523' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fill  
hole with drilling mud to 500', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent