

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 25 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Hanna of Anadarko Prod. Co. has this

date requested permission to plug the following described well:

Mr. Hanna guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351 Liberal, Ks

Lease Name: Ralstin A Well No. 1

Location: NE/SE Sec 31 Twp. 29S Rge 19 (E)(W)W

County: Kiowa Total Depth 5373 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hanna was instructed to plug the well as follows:

517 ft of 10 3/4 surface pipe cemented with 450 sacks. Fill

hole to 500 ft., plug, 1/2 sack hulls, 40 sacks cement. Mud

to 40 ft., plug, 1/2 sack hulls, 15 sacks cement to surface.

2 sacks cement in rat hole. Pumped by Sun Cementing Co.

Very truly yours,

[Signature]
Conservation Division Agent