

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 14 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Shawn of Sage Drlg Co has this

date requested permission to plug the following described well:

Mr. Shawn guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Co

Complete Address: 780 4th Natl Bank Bldg Wichita, KS

Lease Name: Ralstin Well No. 1

Location: C SW/SW Sec. 31 Twp. 29 Rge. 19 (E)(W) W

County: Kiowa Total Depth 5290 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Shawn was instructed to plug the well as follows:

604 ft 8 5/8 surface cemented with 490 sacks. Pump plug,

50 sacks cement to 500 ft. Mud to 40 ft, plug, 1/2 sack

hulls, 15 sacks cement to surface. 2 sacks cement in

rat hole.

Pumped by Sun Cementing Co Great Bend, KS

Very truly yours,

*J. Russell Bickerton*  
Conservation Division Agent