

15-097-10171-0001

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Petrodynamics Inc.

Complete Address Box 10006 Amarillo, TX 79105

Lease Name Robbins Well No. 1-23

Location W/2 SW/NE Sec. 23 Twp. 29 Rge. 17 (E)    (W) W

County Kiowa Total Depth 4750

Abandoned Oil Well    Gas Well X Input Well    SWD Well    D & A   

Other well as hereafter indicated   

Plugging Contractor Daco Lease & Well Service

Address 1700 S. Main Borger, TX License No. 138

Operation Completed: Hour 7:00 PM Day 11 Month 8 Year 1970

The above well was plugged as follows:

320 ft of 8 5/8 surface pipe circulated. 4750 ft of 4 1/2 long string

temp. survey 3700. Top perf. 4624-4629 ft. Pumped 25 sacks cement

to 4500 ft. Set plug. Shot pipe at 3532 ft. Pulled 956 ft of 4 1/2 &

well blew out. Pumped 500 sacks cement & shut in. Shot pipe at 1494

ft. Pulled 2450 ft of 4 1/2 total. Pumped 50 sacks cement through 4 1/2.

Mud to 40 ft. 10 sacks cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 13 1970 8-13-70

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: L. Russell Biberstein  
Well Plugging Supervisor

INVOICED

DATE 8/13/70INV. NO. 2391-W