

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

FORM CP-3
1-8-82
RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1982
CONSERVATION DIVISION
Wichita, Kansas

API Number 15-097-20138

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Petroleum, Inc.

Complete Address P.O. Box 1147, Great Bend, Kans 67530

Lease Name Witt "K" Well No. 1

Location C-NW-NE Sec. 8 Twp. 29S Rge. 19W (East)(West)

County Kiowa Total Depth 5110'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering Inc.

Address Box 698 Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour: 4:00 PM Day: 23 Month: June Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They set 5108' of 4 1/2" production pipe. Then they plugged back to 5042' & perforated from 5015' to 19'. They sanded off bottom back to 4950' & dumped 5 sbp of cement on sand with driller. 2nd plug pumped through 8 5/8" was 6 sbp hulls 25 sbp Jell & released rubber plugs & 150 sbp of cement on rubber plug. The plugging was accomplished by sun cementing. They recovered 2400' of 4 1/2" pipe.

Amount of Surface Casing: 562' of 8 5/8" cement circulate (over)

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luths
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED
DATE 6-29-82
INV. NO. 539-W

The cement used was 50/50 pause with 2% Jell
and 3% C.C. Shut in pressure at 250 lbs

Paul A. Luthi