

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
JAN 13 1967
1-13-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Graham-Michaelis Drilling, Inc.

Complete Address: 211 North Broadway, Wichita, Kansas

Lease Name McChildress Well No. # 1

Location C SW SW Sec. 9 Twp. 29 Rge. 19 (E) (W) W

County Kiowa Total Depth 5120'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Bob Sargent Casing Pulling Service

Address: 121 West 9th, Liberal, Kansas License No. 511

Operation Completed: Hour 5:30PM Day 11th Month Jan. Year 1967

The Above well was plugged as follows:

749' of 9 5/8" surface pipe, cemented with 300 sacks. 5119' of 4 1/2" long string, cemented with 100 sacks. Top perforation 5035'. 12 sacks of cement was pumped on bottom, bringing the top of the cement to 4850' in the 4 1/2" casing. 4556' of 4 1/2" long string was recovered from the hole. 11 sacks of Gel-Mud was pumped into the 4 1/2" casing at 600', 35 sacks of cement was pumped into the 4 1/2" casing at 400'. Fluid was bridged with hulls at 40', and cemented with 15 sacks to the base of the cellar.

This cement was pumped by Sargent Casing Pulling Service.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/13/67

INV. NO. 4601-11

Signed: Arlene Elving
Well Plugging Supervisor