

State of Kansas



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

JUL 18 1962
 7-18-62
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

I have this date 7 - 6 - 1962, 1961, authorized the following plugging operation:

Operator's full Name: Anschutz Oil Co. Inc.
 Complete Address: 350 Denver Hilton Office Building, Denver, Colo.
 Lease Name: Hageman Well No. 3
 Location: SW NE NW Sec. 15 Twp. 29 Rge. 9 (E)(W) X
 County: Kingman Total Depth: 4521'
 Oil Well Gas Well Input Well SWD Well
 D & A Other well as hereafter indicated: _____
Abandoned Oil Well

Operator was instructed to plug well as follows:

5 1/2" pipe set at 4521'. Perforated from 4489' to 4491'.
Sanded to 4470' and 5 sacks cement. 182' surface pipe circulated
with cement. Filled hole with heavy mud to 170' and 10' rock bridge
and 20 sacks cement. Hole filled to 40' and second rock bridge
and 10 sacks cement to bottom of cellar.

Very truly yours,

Herman Justus

