

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

FEB 11 1963

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Perry Daniels of Central Pipe Pulling Co. has this date requested permission to plug the following described well:

Mr. Daniels guarantees payment of the plugging fee.

Operator's full Name: Herman Geo. Kaiser Oil Producer

Complete Address: 909 Palace Bldg., Tulsa 3, Oklahoma

Lease Name: Hageman Well No. # 1

Location: 100' W NW SE NW Sec. 15 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4518 Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Daniels was instructed to plug the well as follows:

4516' of 5½" long string cemented with 200 sacks. Plugged back to 4486'. Perferated 4480' to 4482'. Sanded to 4460'.

246' of 8 5/8" surface pipe circulated with cement. Fill hole with mud to 200', 10' rock bridge, cement with 20 sacks.

Fill hole with mud to 40', 10' rock bridge, cement with 10 sacks to base cellar.

Very truly yours,

Audie Cling  
 Conservation Division Agent