



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 15 1974  
1-15-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Cook of Abercrombie Drlg has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Kathol Petroleum Inc

Complete Address: 230 Sutton Place Wichita, KS

Lease Name: Omo Well No. 1

Location: 100' E of SE/NW/NE Sec. 35 Twp. 28s Rge. 14 (E)(W) W

County: Pratt Total Depth 4200 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Cook was instructed to plug the well as follows:

364 ft 8 5/8 surface cemented with 225 sacks. Pump plug,

40 sacks cement to 600 ft. 2nd plug at 320 ft, 25 sacks

cement. Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks cement

to surface. 2 sacks cement in rat hole.

Pumped by Sun Cementing Co Great Bend, KS

Very truly yours,

Conservation Division Agent